

CASE STUDY

Project – Asbestos Remediation Project at Baker Street Station- Phase II

Location – Baker Street Station – Various Jubilee and Baker Line Locations

Duration – October 2012

Value – Circa £50k, completed on time and within the budget

Scope of Work – Controlled asbestos remediation works incorporating the following activities:

- The removal under fully controlled conditions of melamine faced AIB panels forming cladding to structural elements of the station.
- Released all screws that were fixed to the supporting structure on the tiles.
- The works were undertaken in sealed enclosures subject to negative pressure and respirator zones. Seven enclosures and one respirator zone will be employed for these works.
- The scope included for temporary reinstatement with chicken wire to all areas.



Asbestos Management - Soft Strip Demolition – Fire Risk Assessment – Fire Stopping – Health & Safety Training